




1 / A 1 PERSPECTIVE VIEW
SCALE 1:100




1 / A 2 SITE DEVELOPMENT PLAN
SCALE NTS




1 / A 3 VICINITY MAP
SCALE NTS


DESIGNED BY:	SEAL	R.A. 9266	PROJECT TITLE:	APPROVED BY:	SHEET CONTENTS	DESIGNED BY:	SHEET NO:
ASGAR, CAYOLETTE & SOLANO, LALAINE ENGINEER		DRAWINGS AND COPIES THEREOF AS INSTRUMENTS OF SERVICE ARE THE PROPERTY OF THE ARCHITECT. WORK FOR WHICH THEY ARE MADE MAY BE EXECUTED OR NOT AND ARE NOT TO BE REPRODUCED OR USED IN OTHER WORK EXCEPT BY WRITTEN AGREEMENT WITH THE ARCHITECT.	TWO STOREY RESIDENCY	MARIBETH T. SOLANO OWNER	SITE DEVELOPMENT PLAN VICINITY MAP PERSPECTIVE VIEW	CHECKED BY : DATE: DRAWN BY:	A-1




1 A 2 GROUND FLOOR PLAN
SCALE 1:100




2 A 2 SECOND FLOOR PLAN
SCALE 1:100




5 A 2 REAR ELEVATION
SCALE 1:100




6 A 2 RIGHT SIDE ELEVATION
SCALE 1:100




3 A 2 LONGITUDINAL SECTION
SCALE 1:100



4 A 2 CROSS SECTION
SCALE 1:100




7 A 2 LEFT SIDE ELEVATION
SCALE 1:100




8 A 2 FRONT ELEVATION
SCALE 1:100

DESIGNED BY:	SEAL	R.A. 9266	PROJECT TITLE:	APPROVED BY:	SHEET CONTENTS	DESIGNED BY:	SHEET NO:
ASGAR, CAYOLETTE & SOLANO, LALAINE ENGINEER		DRAWINGS AND COPIES THEREOF AS INSTRUMENTS OF SERVICE ARE THE PROPERTY OF THE ARCHITECT. WORK FOR WHICH THEY ARE MADE MAY BE EXECUTED OR NOT AND ARE NOT TO BE REPRODUCED OR USED IN OTHER WORK EXCEPT BY WRITTEN AGREEMENT WITH THE ARCHITECT.	TWO STOREY RESIDENCY	MARIBETH T. SOLANO OWNER	FLOOR PLANS ELEVATIONS VIEWS SECTION VIEWS	CHECKED BY : DATE: DRAWN BY:	A-2




TYPE	INSTANCE FIXED WINDOW WITH ALUMINUM FRAME	SINGLE AWNING WINDOW WITH ALUMINUM FRAME	DOUBLE SLIDING GLASS WINDOW WITH ALUMINUM FRAME	DOUBLE SLIDING GLASS WINDOW WITH ALUMINUM FRAME	DOUBLE SLIDING GLASS WINDOW WITH ALUMINUM FRAME	FOUR SLIDING GLASS WINDOW WITH ALUMINUM FRAME	FOUR SLIDING GLASS WINDOW WITH ALUMINUM FRAME
LOCATION	2nd Floor Hallway	KITCHEN AREA, LIVING ROOM AREA	BATHROOM 1, BATHROOM 2	LIVING ROOM AREA (1ST FLOOR)	BEDROOM	DINING ROOM AREA	LIVING ROOM AREA (1ST FLOOR)
QTY	6	2	2	1	1	1	1



TYPE	EXTERIOR DOUBLE GLASS WOOD DOOR	INTERIOR SINGLE 1 PANEL WOOD DOOR	INTERIOR SINGLE 2 PANEL WOOD DOOR	INTERIOR SINGLE GLASS WOOD DOOR
LOCATION	LIVING AREA (FRONT)	BATHROOM 1, BATHROOM 2	BEDROOM	LIVING ROOM AREA (1ST FLOOR), BALCONY
QTY	1	2	1	3

1 / A 3 SCHEDULE OF DOORS & WINDOWS
SCALE 1:100



2 / A 3 GROUND & SECOND FLOOR REFLECTED CEILINGPLAN
SCALE 1:100

GENERAL NOTES:

1. GENERAL, Architectural

1.1) These General Notes are instructions to the Contractor and apply generally to all the work unless more specific information is shown in drawings or written in the specifications, standards and/or contracts.

1.2) All construction works shall be in accordance with the most current DWG's, spec's and standards as modified by the Architect/Engineer.

1.3) An approved set of plans shall be maintained on the job site at all times.

1.4) All works shall be conform to the best practice of each trade. Unless shown or noted otherwise, construction details or practices are common to the standard of the trade.

1.5) All works shall be conform to the applicable codes and authority rules.

1.6) The Contractor shall obtain the necessary permits required for the works shown on these drawings prior to the start of the construction.

1.7) The Contractor shall locate and uncover all the underground utilities in advance of the construction in order the Architect/Engineer.

1.8) Backfilling shall not be started until newly installed underground equipment is checked and approved by the engineers to verify their identity and their correct position.

1.9) Backfill shall be installed in accordance with the relevant ruling standards.

1.10) Disposal of/and stockpiling of excess material within the planning area shall be done in such a way that it will not create a nuisance to the ongoing works in general and the neighboring surrounding.

1.11) The Contractor shall not trespass beyond the project boundary lines unless a permit or written authorization has been obtained from the neighboring property owners involved.

1.12) Any damage on public area and/or on the clients premises caused by the ongoing project works shall be restored in its original condition, with no additional cost implication to the owners involved, as per following requirements:

1.12.1) All trees impacted by the ongoing construction works shall be replaced with the
same size and type of tree at the same location or at a new location given by
the local authorities or by the client.

1.12.2) All irrigation systems shall be restored to fully functioning status.

1.12.3) Any road or street cuts are to be coordinated with the local authorities,
backfilled according standards and repaired to its original status.

1.13) All dimensions and levels are in millimeters (mm) unless mentioned otherwise.

1.14) The Contractor shall check and verify all dimensions and levels on site (both new and existing) and report discrepancies to the Architect/Engineer prior to proceeding of works.

1.15) The drawing shall not be scaled. Only written dimensions shall be followed. The Contractor shall request, from the Architect, necessary dimensions not shown on the drawings.


1.16) All Architectural drawings shall be read in conjunction with the Structural, Services drawings and specifications for proper coordination. Any discrepancies shall be brought to the attention of the Engineer.

1.17) All dimensions other than levels are given to structural elements. Dimensions are taken from and to centerlines of columns, beams, and other structural elements; from faces of walls and edges of openings unless shown otherwise.

1.18) All levels shown in the drawing are finished floor levels. Contractor shall allow adequate changes in the structural floor to achieve indicated floor levels.

1.19) Contractor shall submit shop drawings "For Approval" prior to fabrication where required by Architect/Engineer.


DESIGNED BY:	SEAL	R.A. 9266	PROJECT TITLE:	APPROVED BY:	SHEET CONTENTS	DESIGNED BY:	SHEET NO:
ASGAR, CAYOLETTE & SOLANO, LALAINE ENGINEER		DRAWINGS AND COPIES THEREOF AS INSTRUMENTS OF SERVICE ARE THE PROPERTY OF THE ARCHITECT. WORK FOR WHICH THEY ARE MADE MAY BE EXECUTED OR NOT AND ARE NOT TO BE REPRODUCED OR USED IN OTHER WORK EXCEPT BY WRITTEN AGREEMENT WITH THE ARCHITECT.	TWO STOREY RESIDENCY	MARIBETH T. SOLANO OWNER	SCHEDULE OF DOORS & WINDOWS	CHECKED BY : DATE: DRAWN BY:	A-3




BAR SIZE	D1
10mm THRU 28mm.	6d
28mm THRU 36mm.	3d

BAR SIZE	D1
10mm	37.5mm
12mm	50mm
16mm	62.5mm


BAR SIZE (mm.)	D1 (mm.)	180° HOOK (mm.)	90° HOOK (mm.)
10mmØ	60	65	120
12mmØ	72	65	145
16mmØ	96	65	195
20mmØ	120	80	240
25mmØ	150	100	300



1/S1 TYP. REINF. BENDING DET.




2A/S1 TYP. BEAM BAR CUT OFF



2B/S1 TYP. SLAB BAR CUT OFF

2/S1 TYP. BAR CUT OFF DETAILS




HOOK BAR


BAR SIZE (mm.)	Ldh (mm.) TOP BARS	Ldh (mm.) OTHERS
10mmØ	165	150
12mmØ	205	155
16mmØ	270	205
20mmØ	335	255
25mmØ	620	475

STRAIGHT BAR

BAR SIZE (mm.)	Ldh (mm.) TOP BARS	Ldh (mm.) OTHERS
10mmØ	300	300
12mmØ	300	300
16mmØ	400	305
20mmØ	495	380
25mmØ	955	735

3/S1 MIN. HOOKED & STRAIGHT BAR DEVELOPMENT LENGTH






NOTE: FOR REINF. NOT SHOWN FOR CLARITY, SEE FOUNDATION PLAN


GRADE SLAB SCHEDULE (UNLESS OTHERWISE SPECIFIED)

USE	THICKNESS	REINFORCEMENT
DRIVEWAY (RAMP)	127mm.	10mm. @ 300mm. E.W.
MECH. & ELEC. ROOM	127mm.	10mm. @ 300mm. E.W.
WALKS & FLOORS	100mm.	10mm. @600mm. E.W.


4/S1 TYP. SLAB ON GRADE DET.



5/S1 TYP. BEAM CONST. JOINT DET.



6/S1 LINTEL BEAM FOR CMU WALL DET.



7/S1 CHB WALL VERT.REINF. DET.

STRUCTURAL NOTES:

A. GENERAL

1. THE STRUCTURAL DRAWINGS SHALL BE USED IN CONJUNCTION WITH THE ARCHITECTURAL, SANITARY/ PLUMBING AND SPECIFICATIONS.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS AT THE SITE, WHICH INCLUDE THE LOCATION AND DIMENSIONS OF OPENINGS, GROOVES, REGLETS, PIPE SLEEVES, CONDUITS, EMBEDDED OR ATTACHED ITEMS TO CONCRETE, ETC.
3. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY TO PROTECT NEW AND EXISTING CONSTRUCTION, THIS SHALL INCLUDE BUT NOT BE LIMITED TO BRACING AND SHORING FOR LOADS IMPOSED DURING CONSTRUCTION.
4. ALL DIMENSIONS SHALL TAKE PRECEDENCE OVER SCALE SHOWN ON PLANS, SECTIONS, AND DETAILS.
5. GENERAL NOTES AND TYPICAL DETAILS APPLY TO ALL UNLESS OTHERWISE SHOWN OR NOTED.
6. ALL DIMENSIONS ARE IN METRIC SYSTEMS UNLESS OTHERWISE NOTED.
7. ALL BAR DIAMETERS AND SPACING ARE IN mm. UNLESS OTHERWISE NOTED.

B. CONCRETE AND REINFORCING STEEL

1. MINIMUM CONCRETE COVER TO ALL REINFORCING BARS SHALL BE AS FOLLOWS;
   A. CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH_____ 75mm.
   B. FORMED SURFACES EXPOSED TO EARTH OR WEATHER
      10 Ø BARS OR SMALLER_____ 40mm.
      OTHER BARS_____ 50mm.
   C. FORMED SURFACES NOT EXPOSED DIRECTLY TO EARTH OR WEATHER
      SLABS AND WALLS_____ 20mm.
      BEAMS AND COLUMNS_____ 40 mm.
2. REINFORCING BARS SHALL FREE OF RUST, GREASE OR OTHER MATERIALS LIKELY TO IMPAIR BOND.
3. ALL REINFORCING BARS SHALL BE ACCURATELY AND SECURELY PLACED BEFORE POURING CONCRETE OR APPLYING MORTAR OR GROUT.
4. BARS SPLICES SHALL BE SECURELY WIRED TOGETHER. SPLICES IN REINFORCED CONCRETE BEAMS, COLUMNS, AND WALLS SHALL BE AS SHOWN IN DETAILS. FOR NON- STRUCTURAL WALLS, AND MASONRY WALLS, AND SLABS, SPLICES SHALL LAP A MINIMUM OF 40 BAR DIA. AND SHALL BE STAGGERED WHEREVER POSSIBLE.
5. SPLICES REQUIRED IN THE REINFORCEMENT OF BEAMS/GIRDER FRAMING INTO COLUMNS SHALL NOT BE LOCATED WITHIN THE COLUMN NOR WITHIN A DISTANCE OF TWICE THE BEAM/GIRDER FROM THE FACE OF THE COLUMN AT LEAST TWO CLOSED STIRRUP TIES SHALL BE PROVIDED AT ALL SPLICES.
6. LAP SPLICES SHALL BE MADE WITHIN THE CENTER HALF OF COLUMN HEIGHT, AND THE SPLICE LENGTH SHALL NOT BE LESS THAN WHAT IS INDICATED IN THE TABULATED VALUES OF SPLICE LENGTH.

C. MASONRY

1. ALL CONCRETE HOLLOW BLOCKS MASONRY WALLS SHALL BE LAID IN RUNNIN BOND (INTERLOCKING COURSE) WITH FULL MORTAR BEDDING, STACK BOND SHALL BE USED ONLY WHEN SPECIFIED.
2. RECOMMENDED COMPRESSIVE STRENGTH OF CONCRETE HOLLOW BLOCKS SHALL BE 450 PSI (3.10 MPa) OF ITS NET AREA.
3. ALL CELLS SHALL BE SOLIDLY FILLED WITH CONCRETE GROUT.
4. FOR 150mm. THK. CHB: USE 12mm.Ø REBARS
   FOR 100mm. THK. CHB: USE 10mm.Ø REBARS
   VERTICAL SPACING: 500mm.
   HORIZONTAL SPACING: AT EVERY 3 LAYERS


D. EXISTING UTILITIES

UTILITY LINES AND ACCESSORIES INDICATED ON THE DRAWINGS OR FOUND AT THE SITE THAT INTERFERE WITH THE NEW CONSTRUCTION SHALL BE LOCATED AS NECCESSARY.


THA CONTRACTOR SHALL CERTAIN ANY BUILDING PERMIT REQUIRED.

THE CONTRACTOR SHALL ALSO PROVIDE AND GET APPROVAL OF ANY DRAWINGS AND DATA REQUIRED TO OBTAIN DPWH APPROVAL FOR THE RELOCATION.

DESIGNED BY:	SEAL	R.A. 9266	PROJECT TITLE:	APPROVED BY:	SHEET CONTENTS	DESIGNED BY:	SHEET NO:
ASGAR, CAYOLETTE & SOLANO, LALAINE ENGINEER		DRAWINGS AND COPIES THEREOF AS INSTRUMENTS OF SERVICE ARE THE PROPERTY OF THE ARCHITECT. WORK FOR WHICH THEY ARE MADE MAY BE EXECUTED OR NOT AND ARE NOT TO BE REPRODUCED OR USED IN OTHER WORK EXCEPT BY WRITTEN AGREEMENT WITH THE ARCHITECT.	TWO STOREY RESIDENCY	MARIBETH T. SOLANO OWNER	REINFORCEMENT DETAILS STRUCTURAL NOTES SLAB DETAIL BEAM DETAIL	CHECKED BY : DATE: DRAWN BY:	S-1



1 S 2 FOUNDATION PLAN
SCALE 1:100




2 S 2 DETAIL OF COLUMN FOOTING
SCALE NTS

FOOTING MARK	FOOTING SIZE (mm)			REBAR (mm)		SOIL CAPA.	NOTE
	T	L	W	X-DIR	Y-DIR		
F01	250	1350	1350	D16 @400	D16 @400	159	ISOLATED
F02	250	1350	1350	D16 @400	D16 @400	159	ISOLATED
F03	250	1400	1400	D16 @400	D16 @400	159	ISOLATED
F04	250	1750	1750	D16 @250	D16 @250	159	ISOLATED
F05	250	1150	1150	D16 @400	D16 @400	159	ISOLATED
F06	250	1350	1350	D12 @225	D12 @225	159	ISOLATED
F07	250	1400	1400	D12 @225	D12 @225	159	ISOLATED
F08	250	1400	1400	D12 @225	D12 @225	159	ISOLATED
F09	250	1400	1400	D16 @400	D16 @400	159	ISOLATED

3 S 2 FOOTING SCHEDULE
SCALE NTS

MARK	SIZE (mm)	VERTICAL BARS	TIES	
			ENDS	MID
C1	350 x 300	10-16mm ø	2 - 10mm ø @ 20mm	2 - 10mm ø @ 70mm
C2	350 x 300	12-16mm ø	2 - 10mm ø @ 20mm	2 - 10mm ø @ 70mm
C3	300 x 250	8-16mm ø	2 - 10mm ø @ 20mm	2 - 10mm ø @ 70mm

4 S 2 COLUMN SCHEDULE
SCALE NTS




5 S 2 DETAIL OF CONCRETE STAIR
SCALE NTS

NAME	THK. (T1/T2)	LANDING (LEFT)				STAIR				LANDING (RIGHT)				END BAR	LENGTH			SIZE	
		L1	L2	L3	L4	S1	S2	S3	S4	R1	R2	R3	R4		LL	LS	LR	W	H
ST01	200 200	- -	- -	- -	- -	D10 @350	D10 @350	D10 @350	D10 @100	D10 @350	D10 @350	D10 @350	D10 @350	6-	0.000	2000	1000	1000	1400
ST02	200 200	D10 @350	D10 @350	D10 @350	D10 @350	D10 @350	D10 @350	D10 @350	D12 @100	D10 @350	D10 @350	D10 @350	D10 @350	6-	1000	2000	1000	1000	1400


6 A 2 STAIRS REINF. SCHEDULE
SCALE NTS

7 S 2 SECOND FLOOR FRAMING PLAN
SCALE 1:100


DESIGNED BY:	SEAL	R.A. 9266	PROJECT TITLE:	APPROVED BY:	SHEET CONTENTS	DESIGNED BY:	SHEET NO:
ASGAR, CAYOLETTE & SOLANO, LALAINE ENGINEER		DRAWINGS AND COPIES THEREOF AS INSTRUMENTS OF SERVICE ARE THE PROPERTY OF THE ARCHITECT. WORK FOR WHICH THEY ARE MADE MAY BE EXECUTED OR NOT AND ARE NOT TO BE REPRODUCED OR USED IN OTHER WORK EXCEPT BY WRITTEN AGREEMENT WITH THE ARCHITECT.	TWO STOREY RESIDENCY	MARIBETH T. SOLANO OWNER	FOUNDATION PLAN FOOTING DETAIL & SCHEDULE COLUMN SCHEDULE STAIRS DETAIL & SCHEDULE FRAMING PLAN	CHECKED BY : DATE: DRAWN BY:	S-2




1 S 3 ROOF FRAMING PLAN
SCALE 1:100




2 S 3 ROOF FRAMING PLAN
SCALE 1:100




5 S 3 TYP. BEAM DETAIL
SCALE NTS




6 S 3 TYP. TIE BEAM DETAIL
SCALE NTS





3 S 3 TRUSS DESIGN DETAIL
SCALE 1:100




4 S 3 TYP. ELEVATION OF THE TIED COLUMN (SHOWING TIE OR HOOPS SPACING)
SCALE NTS

MARK	BEAM LINE D x B (mm.)	SUPPORT		MIDSPAN		STIRRUPS	
		TOP	BOTTOM	TOP	BOTTOM	SUPPORT	MIDSPAN
GB1	300 x 250	2 - 16mm ø	2 - 16mm ø	2- 16mm ø	2 - 16mm ø	2 - 10mm ø @ 60mm	2 - 10mm ø @ 120mm
GB2	250 x 200	2 - 16mm ø	2 - 16mm ø	2- 16mm ø	2 - 16mm ø	2 - 10mm ø @ 40mm	2 - 12mm ø @ 90mm
B1	350 x 300	3 - 16mm ø	3 - 16mm ø	2 - 16mm ø	2 - 16mm ø	2 - 10mm ø @ 40mm	2 - 10mm ø @ 70mm
B2	300 x 250	3 - 16mm ø	2 - 16mm ø	2 - 16mm ø	2 - 16mm ø	2 - 10mm ø @ 60mm	2 - 10mm ø @ 120mm
B3	250 x 200	2 - 16mm ø	2 - 16mm ø	2 - 16mm ø	2 - 16mm ø	2 - 10mm ø @ 90mm	2 - 10mm ø @ 90mm
RB1	275 x 225	2 - 12mm ø	2 - 12mm ø	2 - 12mm ø	2 - 12mm ø	2 - 10mm ø @ 50mm	2 - 10mm ø @ 100mm
RB2	250 x 200	4 - 16mm ø	2 - 16mm ø	2- 16mm ø	2 - 16mm ø	2 - 10mm ø @ 40mm	2 - 10mm ø @ 90mm

7 S 3 BEAM SCHEDULE
SCALE NTS

DESIGNED BY:	SEAL	R.A. 9266	PROJECT TITLE:	APPROVED BY:	SHEET CONTENTS	DESIGNED BY:	SHEET NO:
ASGAR, CAYOLETTE & SOLANO, LALAINE ENGINEER		DRAWINGS AND COPIES THEREOF AS INSTRUMENTS OF SERVICE ARE THE PROPERTY OF THE ARCHITECT. WORK FOR WHICH THEY ARE MADE MAY BE EXECUTED OR NOT AND ARE NOT TO BE REPRODUCED OR USED IN OTHER WORK EXCEPT BY WRITTEN AGREEMENT WITH THE ARCHITECT.	TWO STOREY RESIDENCY	MARIBETH T. SOLANO OWNER	ROOD FRAMING PLAN BEAM DETAIL & SCHEDULE TRUSS DESIGN MADE MAY BE EXECUTED OR NOT AND ARE	CHECKED BY : DATE: DRAWN BY:	S-3



1/S4 SLAB DETAIL
SCALE NTS

MARK	THK (mm.)	REINFORCEMENTS						REMARKS
		PARALLEL TO SHORT SPAN			PARALLEL TO LONG SPAN			
		ADDITIONAL TOP BARS	BEND BARS	BOTTOM BARS	ADDITIONAL TOP BARS	BEND BARS	BOTTOM BARS	
S2-TR	150	10mm. Ø @ 450mm. o.c.	10mm. Ø @ 450mm. o.c.	10mm. Ø @ 450mm. o.c.	10mm. Ø @ 450mm. o.c.	10mm. Ø @ 450mm. o.c.	10mm. Ø @ 450mm. o.c.	TWO-WAY
S2-BR	150	10mm. Ø @ 500mm. o.c.	10mm. Ø @ 500mm. o.c.	10mm. Ø @ 500mm. o.c.	10mm. Ø @ 500mm. o.c.	10mm. Ø @ 500mm. o.c.	10mm. Ø @ 500mm. o.c.	TWO-WAY
S2-BL	150	10mm. Ø @ 450mm. o.c.	10mm. Ø @ 450mm. o.c.	10mm. Ø @ 450mm. o.c.	10mm. Ø @ 900mm. o.c.	10mm. Ø @ 900mm. o.c.	10mm. Ø @ 900mm. o.c.	TWO-WAY
S1-TL	150	10mm. Ø @ 450mm. o.c.	10mm. Ø @ 450mm. o.c.	10mm. Ø @ 450mm. o.c.	10mm. Ø @ 900mm. o.c.	10mm. Ø @ 900mm. o.c.	10mm. Ø @ 900mm. o.c.	TWO-WAY

2/S4 SLAB SCHEDULE
SCALE NTS

NOTES:

1. IN TWO -WAY SLABS, THE BARS ALONG THE SHORT SPAN BE AT THE LOWER LAYER FOR BOTTOM BARS, AND AT THE UPPER LAYER FOR TOP BARS SO THAT THE BARS ALONG THE SHORTER SPAN SHALL HAVE THE BIGGER EFFECTIVE DEPTH, UNLESS OTHERWISE DETAILED OR NOTED DUE TO THE CONTINUITY OF BARS FROM ADJOINING SPAN.
2. IF THE TOP REINFORCEMENT OVER A COMMON SUPPORT OF TWO ADJACENT SPANS ARE DIFFERENT, THE SMALLER SPACING SHALL BE FOLLOWED OR ADOPTED ON BOTH SLAB PANELS AT THE COMMON SUPPORT.
3. BAR SHALL ONLY BE SPLICE ONLY WHERE INDICATED ON THE DETAILS OR AS APPROVED BY THE STRUCTURAL ENGINEER. STRAIGHT CONTINUOUS BARS IN SLABS MAY BE SPLICED (LAPPED OR WELDED) AT SUPPORTS FOR BOTTOM BARS AND AT MIDSPAN FOR TOP BARS.

NOTES:

1. ALL COLUMNS TIES PER SET SHOULD BE SPACED @ 4 @ 0.05, 4 @ 0.10, REST @ 0.20 M.
2. NO PIPES SHALL BE EMBEDDED INSIDE ANY COLUMN UNLESS OTHERWISE INDICATED ON THE PLAN.
3. ALL PLANTED COLUMNS MUST BE SUPPORTED BY BEAMS OR GIRDER.

DESIGNED BY:	SEAL	R.A. 9266	PROJECT TITLE:	APPROVED BY:	SHEET CONTENTS	DESIGNED BY:	SHEET NO:
ASGAR, CAYOLETTE & SOLANO, LALAINE ENGINEER		DRAWINGS AND COPIES THEREOF AS INSTRUMENTS OF SERVICE ARE THE PROPERTY OF THE ARCHITECT. WORK FOR WHICH THEY ARE MADE MAY BE EXECUTED OR NOT AND ARE NOT TO BE REPRODUCED OR USED IN OTHER WORK EXCEPT BY WRITTEN AGREEMENT WITH THE ARCHITECT.	TWO STOREY RESIDENCY	MARIBETH T. SOLANO OWNER	SLAB DETAIL & SCHEDULE	CHECKED BY : DATE: DRAWN BY:	S-4